KEY NOTES – THIS SHEET

1. NEW 42" HIGH GUARD RAIL WITH MTL. MESH SCREEN
2. NEW HANDRAIL(S)
3. (2) ACCESSIBLE SPACES WITH (6) TOTAL MOVEABLE CHAIRS. CHAIRS N.I.C.
4. NEW PLATFORM, PARTIAL HT. WALLS/RAILINGS FOR ACCESSIBLE SEATING – (4) LOCATIONS
5. EXISTING CONC. PILASTERS REINFORCED AS PER STRUCTURAL
6. NEW COMMUNITY BULLETIN BOARD OVER NEW FURRING AND GWB
7. REPLACE EXIST. AREAWAY GRATE WITH 6'–1" X 8'–0" NEW GRATE WITH 24"x 30" ACCESS HATCH
8. NEW COUNTER AND NEW PARTIAL HEIGHT INFILL WALL BELOW COUNTER TO MATCH EXISTING
9. RELOCATED EXISTING SCISSOR GATE
10. NEW STAIRS
11. NOT USED △1
12. NEW AUTOMATIC DOOR OPENER FOR ADA ACCESS
13. NEW STEEL PILASTER AS PER STRUCT.
14. 'MAX. OCCUPANCY 49' SIGN △1
15. 'MAX. OCCUPANCY 862' SIGN
16. INFILL EXIST. OPENING WITH ONE HOUR WALL TO MATCH
17. NEW ALUM. STOREFRONT SYSTEM AND DOORS TO REPLACE EXIST. ENTRY. ALTERNATE #2 ONLY.
18. NEW ENTRY WALK–OFF MAT W/ RUBBER CARPET BAR AT EDGE

LEGEND – THIS SHEET

FOUR–HOUR SEPARATION WALL

X WALL TYPE (SEE SHEET A601)

AREAS OF NO OCCUPANCY THIS PERMIT

TILE PATTERN

SCALE: 1/4" = 1'-0"

ALTERNATE CHARCOAL AND GARNET, EVERY OTHER ROW

ALTERNATE SANDSTONE AND SABLE, EVERY OTHER ROW

ALTERNATE #2

MAIN FLOOR PLAN

SCALE: 1/8" = 1'-0"

NORTH

0 2 4 8 16 24

1/8" = 1'-0"

ARAI/JACKSON
Architects & Planners
1601 East John • Seattle, WA 98112
Tel: 206-323-8800 Fax: 206-323-8518

CONSTRUCTION DOCUMENTS BID SET

REGISTERED ARCHITECT STATE OF WASHINGTON

NO.	REVISION – AS BUILT	DATE
3		
2	OWNER REVISIONS △2	4/24/03
1	PERMIT CORRECTIONS △1	7/15/02

REVIEWED:
PARK ENGINEER DATE

All work done in accordance with the City of Seattle Standard Plans and Specifications in effect on the date shown above, and supplemented by Special Provisions.

SAND POINT
MAGNUSON PARK
COMMUNITY RECREATION CENTER
BUILDING 47

MAIN FLOOR PLAN

DESIGNED	KS, MB	DATE	APR. 24, 2003
DRAWN	KS, MB, MO	DESIGN REVIEW	
CHECKED	GO, JA		
ORDINANCE NO.	119612 & 119987		
CONTRACT NO.	1616	SHEET	8 OF 76
SCALE	AS NOTED		

A202

Spec–0202